

# Takeoff Tab

**\*ASAP Swimkids Building and Pool P - MAPR17-00329**

Bid No. 33

No.	Name	Height	Area	Quantity1 UOM1	Quantity2UOM2	Quantity3 UOM3
<b>Steps</b>						
22	Steps	0"	(unassigned)	12 EA	0	0
<b>Sog</b>						
20	4" sog	0"	(unassigned)	6,059 SF	75 CY	534 LF
<b>Sidewalks</b>						
17	Sidewalks	0"	(unassigned)	533 SF	7 CY	0
19	6" Trash Enclosure Slab	0"	(unassigned)	72 SF	1 CY	0
<b>footing wall</b>						
12	CW10-10A	4' 0"	(unassigned)	434 LF	59 CY	0
26	CW16-16A	4' 0"	(unassigned)	42 LF	9 CY	0
27	CW8-8A	4' 0"	(unassigned)	54 LF	6 CY	0
<b>footing</b>						
11	fs4.0	1' 3"	(unassigned)	6 EA	4 CY	0
<b>Cont Footing</b>						
1	FC1.5 - Cont Footing 12"	1' 0"	(unassigned)	20 LF	1 CY	0
2	FC2.0 - Cont Footing 12"	1' 0"	(unassigned)	523 LF	39 CY	0
3	FC2.5 - Cont Footing 12"	1' 0"	(unassigned)	34 LF	3 CY	0
25	FTS2.0 - Cont Footing Trash encl	1' 8"	(unassigned)	18 LF	2 CY	0
<b>Curb &amp; Gutter</b>						
23	Curb & Gutter	2' 0"	(unassigned)	661 LF	61 CY	0
<b>Concrete Entry Apron</b>						
24	Concrete Entry Apron	0"	(unassigned)	194 SF	2 CY	0